Synchronizing Small Cells





www.calnexsol.com

Presentation overview




- Small Cell Sync Requirements
- Deployment Types
- Measuring Small Cell Synchronization

Where do you start?



Diverse landscape, multiple architectures, multiple technologies





Small Cell Sync Requirements

"Air Interface" Sync Requirements



no requirement

no requirement

 $\pm 0.5 - 5 \mu s^*$

± 1.5μs

Frequency requirements:

- Carrier small cell: 100ppb
- Residential small cell: 250ppb

Time requirements:

- LTE FDD with no co-ordination:
- LTE TDD with no overlapping coverage:
- LTE TDD with overlapping coverage:
- LTE FDD or TDD with elClC or CoMP:
- E911 OTDOA (Observed Time Difference of Arrival): ± 0.1µs
 - * Depends on technology and throughput requirements 3GPP have stated it will never *require* better than ± 1.5µs

Frequency Sync Delivery Requirement






Figure 4/G.8261.1 – Output wander network limit for case 3 based on [ITU-T G.823]

Time Sync Delivery Requirement



Air interface requirements, less:

- 150ns for basestation internal tolerances
- 250ns for short term holdover (e.g. to allow reference switch)

Example for LTE TDD:

- $\pm 1.5 \mu s$ at the air interface
- ±1.1µs at the network interface

Example for LTE CoMP (tightest tolerance):

- ±500ns at the air interface
- ±350ns at the network interface (no reference switching)

Coming Soon...



- CRAN Architecture
 - Baseband units co-located, fronthaul network used to distribute baseband signals to remote radio units
 - Common interface standards: CPRI, OBSAI
- NGFI: Next Generation Fronthaul Interface
 - Evolution of fronthaul to use Ethernet with PTP/SyncE time synchronization
 - Required for future "5G" radio requirements
- Frame Time Alignment Requirements between RRUs:
 - Inter-band carrier aggregation:
 - Intra-band carrier aggregation:
 - MIMO and TX Diversity:

1325ns frame time alignment


- 155ns frame time alignment
- 65ns frame time alignment



Deployment Types


AT&T In-Building Proposal





In-Building Network Diagram






Street deployment



Urban canyons, microwave backhaul


- Poor GNSS environment, multipath reflections and restricted sky view
- Backhaul typically NLOS or LOS microwave



Small Cell Microwave Backhaul



- Microwave equipment often includes PTP support, e.g. BC or TC
- What performance standards must the BC or TC function meet?




C-RAN Architecture



Remote

Radio Units

- Centralizes Baseband Units (BBUs) in a "baseband hotel"
- BBUs all co-located, simplifying sync for eICIC and CoMP
- Requires accurate latency measurement of "fronthaul" network to synchronize RRUs






Measuring Small Cell Synchronization

Distributed BC and TC




• What should the performance spec be for a distributed BC/TC function (e.g. microwave unit)?



- Current BC spec (G.8273.2) is for a single network element
- Proposal for a "distributed BC/TC":
 - Based on sum of two G.8273.2 BCs
 - G.8171.1 HRM can remain unchanged; distributed BC uses two nodes

Microwave Test Configuration



Tests to apply:

- Noise generation (±100ns cTE, 50ns p-p dTE proposed)
- Noise tolerance (from network limit, possibly 1.1µs max|TE|, 500ns p-p dTE)
- Noise transfer (tests filtering capability)

Calnex

How to measure small cell sync



1. At the sync interface output

- **BUT** most small cells don't have extra outputs such as sync interfaces
- Possibly a test point is accessible in the lab, but not in a field environment

2. At the network interface


- Probe PTP flow at network interface, then the originTimestamp in the Delay_Req message (T3) gives a direct readout of internal clock state
- **BUT** PTP devices are not required to insert an accurate T3 value
 - IEEE1588-2008, Clause 11.3.2: "The originTimestamp shall be set to 0 or an estimate no worse than ±1 s of the egress time of the Delay_Req message."
 - Requires on-the-fly hardware timestamp insertion, which is only mandated for one-step PTP master

3. At the air interface

• Monitor the RF output signal, decode frames for frequency and alignment

Lab Test Configuration






Tests to apply:

- Noise generation and tolerance for frequency (from G.8263)
- Noise generation and tolerance for time (to be determined)
- Noise transfer (tests filtering capability)

Field Test Configuration






PTP Field Tester monitors:

- Quality of sync coming from PRTC/GM
- Accuracy of small cell sync (if accurate T3 available)

Over-the-air Sync Test Configuration





PTP Field Tester monitors:

- Frequency and time sync of RF output
- Non-invasive method; no disconnection required to insert tap



INTEGRITY

TIME ERROR MEASUREMENTS REQUIRE TRUE PRECISION

Tommy Cook tommy.cook@calnexsol.com +44 (0) 1506-671-416